

Legacy Building and Exteriors

RECIPIENT:

Long Valley Charter School

436 Susan Drive
Doyle, California 96109

Quote #29

Sent on

Feb 11, 2026

Total

\$47,540.00

Product/Service	Description	Qty.	Unit Price	Total
Standing seam metal roof	<p>Remove all rock, and adhesive rolled roofing moisture barrier off of 76' wide x 39' long roof, and three 5x12 awnings.</p> <p>Haul all old roofing materials to landfill.</p> <p>Inspect all roof sheeting for damage or rot. (Contractor will cover up to \$500 of unseen damages, any unseen damage beyond \$500 will be an additional cost to Long valley Charter School)</p> <p>Re-nail off all sheeting as required by Lassen county code, and will be signed off by county Inspector.</p> <p>Install synthetic ice and water shield barrier on main roof and awnings.</p> <p>Install eve trim and gable trim.</p> <p>Install 16" wide standing seam hidden fastener metal on 39'x76' main roof, and x3 5'x12' awnings.</p> <p>Eve edges will be hemmed over eve trim, and rib ends covered to prevent bugs, bees and, debris.</p> <p>Install vent boots over vents in roof, and seal edges to prevent leakage.</p>	1	\$47,540.00	\$47,540.00*

* Non-taxable

Total

\$47,540.00

We are committed to ensuring that our projects proceed as smoothly and efficiently as possible. Our team takes pride in their work, with the objective of achieving satisfaction for both the customer and the contractor.

Thank you for the opportunity to quote on this project!

This quote is valid for a period of 30 days, after which prices may be subject to change.

The quoted price encompasses all materials and labor required to complete the project as outlined in the description.

The contractor will obtain the necessary permit, and the associated cost is included in the total price.

The property will be meticulously cleaned of any debris and waste related to the project.

All debris and waste materials will be removed, ensuring that the property is left in a better condition than it was found.